

ITEM 40

FENCE RELOCATION

40.01 DESCRIPTION

This item shall consist of the relocation of all types of fence complete-in-place. The contractor shall use existing materials in the relocation. All fence shall be relocated to as close to the original state as is possible. Any new material required shall be furnished by the contractor and shall meet the specifications as set out in this item.

40.02 MATERIALS

The fabric, line post, corner post, etc., shall be of the same quality and meet the same requirements as set out in the A.S.T.M. specifications for the original material.

40.03 CONSTRUCTION

All fence shall be erected to the lines and grades as indicated on the plans or as directed by the Engineer.

(a) Chain Link Fence

(1) All posts in the line of fence shall be spaced not further apart than 10' center to center. All posts shall be set in concrete bases, and the posts shall extend in the concrete not less than 26". The concrete bases shall be at least 8" in diameter and extend 30" or more below the surface of the ground. The concrete bases shall be crowned at the top to shed water and shall be finished to the satisfaction of the Engineer.

(2) The fabric shall be fastened to the top rail at intervals not exceeding 24" and to posts at intervals not exceeding 14".

(3) The top rail shall be connected with expansion sleeves to form a continuous rail.

40.04 METHOD OF MEASUREMENT

Fence will be measured by the linear foot of fence complete and accepted in place measured in the line of the fence.

40.05 BASIS OF PAYMENT

(a) All fence relocation shall be paid for at the contract unit price for fence relocation, which price shall be full compensation for the construction of the item as indicated above, including all materials, equipment, tools, labor, and incidentals required to complete the item.

(b) Payment will be made under Item No. 40, fence relocation per linear foot.

END OF DOCUMENT